



## Panel Installation Instructions

- Installation contractor and crew shall be totally familiar with all means and methods required for a compliant and approved finished installation.
- Carefully review contract documents and approved submittals.
- Verify that all required substrates are properly framed, installed, and ready for required and proper installation of all metal panel components.
  - Examine substrates with substrate installer present.
  - Verify compliance with requirements for installation tolerances of metal components and other conditions affecting final installation metal panel components on substrate.
  - Studs should be placed 8 inches on center to fit the metal panel components. Coordinate metal panel component size selection with stud spacing.
  - Proceed only after all substrate defects have been corrected.
- Verify that all metal panel components are properly contained in protective shipping and storage packaging.
- Only remove metal panel components from protective shipping and storage packaging as installation progress requires. Inspect for any marks, defects and damage that would prevent required installation results. Notify factory representative at once for expedient delivery of replacement metal components.
- Install metal components in strict accordance with approved shop drawings and manufacturer's printed supplemental instructions to achieve required finished installation. All cuts shall be hairline true, and free of burrs and gouges.
- Provide a sequential attachment process using mechanical fastener methods so as to prevent damage to any surfaces of the metal panel components.
  - Mechanical fasteners shall be placed in holes so as to engage studs.

- Remove debris at the end of each day's activities and carefully protect until subsequent installation continues.
- Remove all tools, equipment, and packaging and scrap materials.
- Provide final cleaning of work area.
- Properly clean and protect finished metal panel installation.
- Review completed installation with manufacturer's, owner's and Contractor's representatives in attendance for final acceptance. Document meeting.